



# Florida Roof Testing Services, Inc.

Phone: 954.566.1399

Fax: 954.566.1329

## 2008 FEE SCHEDULE FOR TESTING, ENGINEERING AND INSPECTION SERVICES

### TESTING \* ENGINEERING CALCULATIONS \* INSPECTIONS

Since 1998

<b>Tile Uplift Test / TAS 106</b>	25 mile radius of Oakland Park	Local	\$210.00
Up to 5,000 sf + \$10. ea addl. 1,000 sf.	*North of Boynton Beach	*NOB	\$225.00
	*South of Hialeah	*SOH	\$225.00
<b>Tile Re-Test:</b>			\$50 local / \$75 *NOB / *SOH
<b>Test Report Copies:</b>			\$35.00

<b>Fastener Pull Test / TAS 105</b>	Minimum 10 Pulls Per Level (FBC)		
	Concrete, Steel or Wood Deck	\$40.00 per pull	\$400.00
	LWC, Gypsum, Tecktum Deck	\$45.00 per pull	\$450.00
FBC- First 10,000 sf requires 10 pulls minimum, each additional 5,000 sf requires 3 additional pulls.			
FBC- For LWC, Gypsum or Tecktum decks 25% more pulls are required.			

<b>Wind Uplift Test- TAS 124</b>			
Bell Chamber or Bonded Pull			
FBC- First 10,000 sf requires 3 pulls minimum, each additional 5,000 sf requires 1 additional pull.			
	Smooth Surface Roof		\$900.00
	Additional Test Smooth Surface		300.00
	Gravel Surface Roof		1,050.00
	Additional Test Gravel Surface Roof		350.00

<b>Roof Moisture Survey &amp; Gravimetric TAS 126</b>	up to 20,000 sf	\$800.00 minimum charge
	over 20,000 sf	\$0.04 per sq ft

<b>Engineering Calculations: ASCE 7 Contractor Supplied Information</b>	Base Sheet Attachment	\$300.00
	Insulation Board Attachment	\$300.00
	Wood Blocking Attachment	\$300.00
	Wood deck Attachment	\$300.00
	Roof Recover Attachment	\$300.00
	Drainage Calculation	\$450.00
	Site visit to obtain information	\$200.00

<b>Asbestos Testing</b>	10,000 sf	425.00
	20,000 sf	475.00
	30,000 sf	550.00
	40,000 sf	625.00
	50,000 sf	700.00
	60,000 sf	775.00
	70,000 sf	850.00
	80,000 sf	925.00
	900,000 sf	1,000.00

<b>Missed Inspection</b>	\$350.00 Broward County
<b>Tin Cap / Mop / Tile / Deck Nail</b>	\$400.00 *Dade & Palm Beach County
Local Building Codes- Require minimum three 3'x3' cuts, for first 2,000 sf plus one additional cut each additional 1,000 sf.	